305

TUMKUR DIVISION.

FORM OF ADVERTISEMENT.

Notification dated 13th February 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 2 P.M., on 20th February 1928, for constructing a causeway across Keggerehalla on Nademavinpur-Amruthur Road. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. Plans, detailed estimate and conditions may be seen at the Executive Engineer's Office, at Tumkur, between the hours of 11 A.M. and 5 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained form the Executive Engineer. The tender should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred and fifty only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a causeway across Keggerehalla on Vademavinpur-Amruthur Road, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The rate should be noted both in figures and in words in the form without any corrections or additions under items of work.

10. No claims for any higher rate on any account will be entertained after the tender is accepted.

11. The contractor will be dealt with in terms of his bond for any short progress or delay.

12. In matters of all disputes about rates, measurements quantity of work, etc., and in all disputes of any kind the decision of the Chief Engineer will be final and legally binding.

Approximate quantity of work for constructing a causeway across Keggerehalla on Nademavinpur-Amruthur Road.

No.	Items of work	Per	Quantity	Rate			
				In figures			In words.
				Rs.	a.	p.	Rs.
1	Earthwork excavation in sandy soil ...	C.yd.	515				
2	Rough stone work new with 2½ miles lead ...	"	639				
3	Burnt stone slabs 8" thick roughly dressed ...	S.ft.	1336				
4	Earthwork excavating, side drains ...	C.yd.	327				
5	Collecting and stacking gravel with ½ mile lead	"	218				
6	Consolidation of gravel with picking spreading, etc.	"	218				
7	Forming the approaches of road ...	Lump sum					
8	Removing and refixing mile and furlong stones	Lump sum					

Abstract Notification.

The attention of the public is invited to the notification published at page 37, Part of the *Mysore Gazette*, dated 26th January 1928, calling for tenders for maintenance wo to Maidala tank in the Tumkur Taluk. The last date for presentation of the tender is 20th February 1928 and not 20th July 1928.

V. V. PATANKAR,
Executive Engineer.